

## Addendum-5

In addition to Addendum-1 , Addendum-2, Addendum-3, Addendum-4 please find following additional data of e-tender SKI6639P18/08 provided as clarification against queries asked:

<b>Query</b>	<b>Clarification. Additional data of SKI6639P18/08</b>
We understand total height of control room is 3 meters (From true floor to true ceiling). Any false flooring or false ceiling exists inside the control room?	No.
Kindly confirm type of detection and gas release panel required (Conventional or addressable ?)	It is not fixed as the system is going to be installed in OIL LPG plant for the first time. So, please provide whichever is better and generally convenient for use.
Approval required for detection cum gas release system?	All equipment shall be approved by UL/FM/Vds/LPC and cylinders along with cylinder valve assemblies shall be seamless and PESO/CCoE approved.
Details about existing fire alarm system on site. If any ? Discharge indication on existing FAP required or not?)	Discharge indication is not mandatory.
Your specification asked for Inert Gases , mean only Nitrogen based gases like IG 55 or IG 541, Your comments written as any clean agent as per NFPAp2001, means IG and FM 200 & Novec 1230.	Any clean agent as per NFPAp2001 is acceptable.

All other terms and conditions of the tender remain unchanged.